

Notice Inviting Short Tender
OFFICE OF THE CIVIL SURGEON DH MORENA
(GWALIOR DIVISION)


NIT. No. / SHORT tendering/ 02

Dated15/02/2022

percentage rate bids for the following works are invited from registered contractors and Firms of repute fulfilling registration criteria:

S. No. /Pkg/ Code	Name of Work	District (s)	Probable Amount of Contract (Rs. in lakh)	Period of Completion
1	Repairs maintenance & Renovation work of lali hariyali ward and pnc ward dr duty room and toilet renovation in dh morena	Morena	Rs 496430	15 Days Including Rainy Season from date of Issue of work Order

1. Interested bidders can view the detailed NIT on the website <https://dhmorena.in>
2. The Bid Document can be purchased/upload only online from 16.2.2022 to 22.2.2022 6 pm
3. Amendments to NIT, if any, would be published on website only, and not in newspaper.


Civil surgeon
District Hospital morena mp
सिविल सर्जन सह मुख्य अस्पताल अधीक्षक
जिला चिकित्सालय मुरैना (मध्य प्रदेश)

Notice Inviting Short Tender
OFFICE OF CIVIL SURGEON DH MORENA


NIT.No. /2021-22 /short tendering/MORENA /01

Dated .15.10.22/2022

percentage rate bids for the following works are invited from registered contractors and Firms of repute fulfilling registration criteria:

S. No. /Pkg/ Code	Name of Work	District (s)	Probable Amount of Contract (Rs. in lakh)	Earnest Money Deposit (EMD) (In Rs.)	Cost of Bid Document	Category of Contractor	Period of Completion
1	2		3	4	5	6	7
1	Repairs maintenance & Renovation work of lali hariyali ward and pnc ward dr duty room and toilet renovation in dh morena	Morena	Rs. 496430	Rs. 20,000.00	Rs. 500/--	PWD Registration	15 Days Including Rainy Season from date of Issue of work Order

- All details relating to the Bid Document(s) can be viewed and downloaded free of cost on the website <https://dhmorena.in>
- निविदाकार को सीमित निविदा को नियमानुसार कार्यालय में जमा करना होगा । एक (अ) लिफाफे में सामित निविदा में चाहे गये वाछित दस्तावेज एवं दूसरे (ब) लिफाफे में कार्य की दर सीलबंद कर उक्त दोनो लिफाफो को एक बड़े लिफाफे में सीलबंद कर कार्यालय में दिनांक 16/2/2022 से 22/2/2022 शाम 06 बजे तक डाक, कोरियर एवं स्वयं के माध्यम से जमा किया जा सकेगा । उक्त लिफाफो पर निविदाकार का नाम पूर्ण पता अंकित होना अनिवार्य होगा ।
- उपरोक्त कार्य को लोक निर्माण विभाग एवं म0प्र0 शासन के निर्धारित नियमानुसार इस कार्यालय द्वारा निर्धारित संबंइजीनियर एवं उपयंत्री के मार्गदर्शन में सम्पादित करना अनिवार्य होगा ।
- निविदा को स्वीकृत करने का अधिकार सिविल सर्जन मुरैना को रहेगा । इसमें किसी भी प्रकार की दावे आपत्ति स्वीकार नहीं की जावेगी ।
- निविदा फार्म को क्रय किये जाने की राशि का बैंकर्स चैक जो कि सचिव रोगी कल्याण समिति जिला चिकि0 मुरैना के नाम से देय होगा को निविदा के (अ) लिफाफे में वाछित दस्तावेजो के साथ मूलतः रखना अनिवार्य होगा । अन्यथा संबधित की सीमित निविदा स्वीकार नहीं की जावेगी । जिसकी समस्त जिम्मेदारी संबधित की होगी ।
- निविदा की धरोहर राशि 20,000/- को एफ.डी.आर. के रूप में जो कि सिविल सर्जन सह मुख्य अस्पताल अधीक्षक जिला चिकि0 मुरैना के नाम से देय होगी को निविदा के (अ) लिफाफे में वाछित दस्तावेजो के साथ मूलतः रखना अनिवार्य होगा । अन्यथा संबधित की सीमित निविदा स्वीकार नहीं की जावेगी । जिसकी समस्त जिम्मेदारी संबधित की होगी ।
- कटी हुई दर स्वीकार नहीं की जावेगी ।
- सभी दस्तावेज निविदाकार द्वारा स्वयं प्रमाणित किया जाना अनिवार्य होगा ।
- निविदा को दिनांक 23/2/2022 को दोपहर 03 बजे समिति के समक्ष खोला जावेगा । जिसमें निविदाकार स्वयं अथवा उनका प्रतिनिधि उपस्थित रह सकते हैं इसकी प्रथक से कोई सूचना नहीं दी जावेगी ।


CIVIL SURGEON
DISTRICT HOSPITAL MORENA MP.
सिविल सर्जन सह मुख्य अस्पताल अधीक्षक
जिला चिकित्सालय मुरैना (म0प्र0)


Repairs maintenance & Renovation work of lali hariyali ward and pnc ward dr duty room and toilet renovation in dh morena की आमंत्रित सीमित निविदा में वांछित दस्तावेज

सीमित निविदा लिफाफा "अ"

1. राशि 500/- का बैंकर्स चेक जो कि सचिव रोगी कल्याण समिति जिला चिकित्सालय मुरैना के नाम देय हो ।
2. राशि 20,000/- (बीस हजार) की एफ.डी.आर जो कि सिविल सर्जन सह मुख्य अस्पताल अधीक्षक मुरैना के नाम देय हो ।
3. लोक निर्माण विभाग म0प्र0 में जीवित पंजीयन ।
4. स्थापना जीवित पंजीयन ।
5. जी.एस.टी. पंजीयन
6. पेन कार्ड
7. फर्म का विगत 03 वर्ष (2017-18ए 2018-19 एवं 2019-20) का टर्न ओवर प्रमाण पत्र चार्टर्ड एकाउंट द्वारा प्रमाणित ।
8. विगत 03 वर्ष में लोक निर्माण विभाग दर पर किये गये कार्यों का अनुभव कार्य आदेश की प्रति
9. 10 रु. के स्टाम्प पर केन्द्र सरकार राज्य सरकार एवं अशासकीय संस्था में ब्लेक लिस्टेड नहीं होने का शपथ पत्र

सीमित निविदा लिफाफा "ब"

1. दर निर्धारित प्रपत्र में


सिविल सर्जन सह मुख्य अस्पताल अधीक्षक
जिला चिकित्सालय मुरैना (म0प्र0)

पृष्ठ " १ "

प्रति .

सिविल सर्जन सह मुख्य अस्पताल अधीक्षक
जिला चिकित्सालय मुरैना म0प्र0

विषय :-

दर प्रस्तुत करने बावत् ।

S. No. /Pkg/ Code	Name of Work	District (s)	Probable Amount of Contract (Rs. in lakh)	Rate
1	2	3	4	5
1	Repairs maintenance & Renovation work of lali hariyali ward and pne ward dr duty room and toilet renovation in dh morena	Morena	Rs. 496430	

फर्म का नाम

पता

मोबाइल नं.

फर्म की सील

15/11/20

TECHNICAL- REPORT

Of Work :-

Estimate for Repairs Maintenance & Renovation work of lali hariyali ward and pncward dr duty room and toilet renovation in DH MORENA

Estimated Civil Work Rs. 496430

Authority :-

Year :- 2021-22

Head:- state head

Necessity :- As per site Instruction given by EE NHM Div. Gwalior Estimate has been framed.

Provisions:- Following provisions has been made in the Estimate.
1 civil work

Technical Sanction:- Executive Engineer NHM /Director, Health service, Bhopal

Rate:- As Per Schedule of Rates for building work issued by Engineer in Chief Govt. of M.P. Bhopal w.e.f. 01/12/2020 and Amended up to date.

Agency:- By contract system

Sub-Engineer
Health Services morena

Assistant engineer
gwalior division

सिविल सर्जन सह मुख्य अस्पताल अधीक्षक
जिला चिकित्सालय मुरैना (म०प्र०)

**or Repairs Maintenance & Renovation work of lali hariyali ward and pncward dr
duty roon anfd toilet renovation in DH MORENA**

A. CIVIL WORK

JR Item	Item	MEASUREMENT									
		No.	L	W	D:H	Qty	Unit	Rate	Amount		
2	3	4	5	6	7	8	9	10	11		
1	15.45	Dismantling of flushing cistern of all types (C.I. PVC Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.		8				8.00	Each	223	1784
2	15.2	Demolishing cement concrete manually by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-Charge									
3	15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix).									
		OLD BUILDING		1	17.5	0.05	12.4	10.85			
				1	9	0.05	8	3.60			
								14.45	Cum	578	2081
4	22.19	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer, 3mm thick water proofing membrane, black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane a 0.40 ltr sqm. by the same membrane manufactured of density at 25°C, 0.87 - 0.89 kg/ltr and viscosity 70 - 160 cps. Over the primer coat the layer of									
		OLD Medical WARD		1	17.5		12.4	217.00			
								217.00	SQM	440	95480
6	11.39	11.39 Mirror polishing on marble work/Granite work/stone work where ever required to give high gloss finish complete.									
		Mirror polishing rooms		1	3	5.5		16.50			
								16.50	Sqm	269	4439
7	15.48	15.48 Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.									
		OLD BUILDING		1	12.4		4.5	55.8			
				1	38.6		4.5	173.7			
				1	4	8	8	32			
				1	10	6	6	60			
				1	5	5	5	25			
								346.5	Sqm	13	4505
8	13.3.2	20 mm cement plaster of mix :1:6 (1 cement : 6 sand)									
		Same Qty of Dismantling of old plaster						145	Sqm	197	28565

Item	MEASUREMENT							
	No.	L	W	D/H	Qty	Unit	Rate	Amount
	4	5	6	7	8	9	10	11
2.6	2.6 Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including dressing of sides and ramming of bottom disposal of excavated earth. lead upto 50m and lift upto 1.5m. disposed earth to be levelled and neatly dressed. (No extra lift is payable if work is done by mechanical means) All kinds of soil							
	1	4.5	3.5	2.5	39.38			
					39.38	Cum	129	5079
2.9	Excavating trenches of required width for pipes, cables, etc. including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m. (No extra lift is payable if work is done by mechanical means) in all kinds of soil							
2.9.1	<80mm dia Pipes, cables etc. not exceeding 80 mm dia.							
	40				40.00	Mtr	96	3840
10	4.1 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : With 40 mm nominal size graded stone agg.							
	M10							
	1	4.5	3.5	0.1	1.58			
					1.58	cum	3808	5908
5.9.1	Centering and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns, etc. for concrete upto plinth level							
	1	4.5		0.1	0.45			
					0.45	sqm	190.6	86
5.1.1	Providing and laying in position specified grade of reinforced cement concrete (with 20mm nominal size graded stone aggregate) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level							
	1	4.5	3.5	0.1	1.58			
					1.58	cum	5796	9129
5.16.6	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding including cost of binding wire all wastages and overlaps, couplers (overlaps shall							
	tmt							
					140.00	kg	62.9	8806
	qty of rec 80 kg/cum							
6.7.1	Brick work with fly ash lime bricks (FALG Bricks) conforming to IS:12894-2002, in super structure above plinth level up to floor two level in :							

MEASUREMENT

Item						Qty	Unit	Rate	Amount
	No.	L	W	DH		8	9	10	11
3	4	5	6	-		8			
OLD BUILDING	1	4.5	2	2.25		2.03			2.03
						2.03	Cum	5162	10453
5.1.1									
12 mm cement plaster									
12 mm cement plaster of mix	1	4.1		2.25		9.23			9.23
Surgical ward Septic Tank						9.23	Sqm	138	1273
7.29									
Providing and fixing horizontal chajja of stone 40 mm thick and upto 80 cm projection in cement mortar 1:4 (1 cement : 4 sand) including pointing in white cement mortar 1:2 (1 white cement : 2 marble dust) with an admixture of pigment matching the stone sha									
OLD BUILDING	1	2.54	3.5			8.89			8.89
						8.89	Sqm	744	6614
5.9.1									
Foundations, footings, bases of columns, etc. for concrete upto plinth level									
Drainage Line	1	41	1.2	0.15		7.38			7.38
						7.38	Sqm	190	1402
5.1.2									
Providing and laying in position specified grade of reinforced cement concrete (with 20mm nominal size graded stone aggregate) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :									
OLD BUILDING	1	2	3.5	0.1		0.70			0.70
						0.70	cum	5397	3778
5.16.6									
Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding including cost of binding wire all wastages and overlaps, couplers (overlaps shall									
tm)									
qty of rcc 90 kg cum									
10.15 Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses frame work etc. including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.									
10.15.1 Hot finished welded type tubes									
	1	2	3.6			7.2			7.2
						7.2	Sqm		7.2
						180	Kg	109	19620
25kg/Sqm									
12.15									
Providing and fixing precast galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm + 0.05 %, total coated thickness with zinc coating 120 gsm as per IS: 277 in 240 mpa steel grade. 5-									
	1	2	3.8			7.6			7.6
						7.6	Sqm	652	4955
15.11.272									
Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead for thickness of tiles 10 mm to 25 mm									
15.11.1									
For thickness of tiles 10 mm to 25 mm									
Male ward Wall Tiles	1	6.6	2			13.2			13.2
	1	23.4	2			46.8			46.8
	6	18	1.8			19.44			19.44

Item	No.	L	W	D H	Qty	Unit	Rate	Amount
	4	5	6	-	8	9	10	11
3								
Female Ward								
				Total	106.66	Sqm	17	1813.22

18	11.76	Providing and laying vitrified floor tiles (without soluble salt) or printed (with soluble salt) Nano polished (Glossy finish) in different sizes with water absorption less than 0.05% and conforming to IS:15622 of approved make in all colours & shades. 1st quality/ premium quality in flooring laid on											
	11.76	Size of Tile 600x600x9-10 mm				1	13.4	2.6	34.84				
		Male ward (Floor Area) Gallery							Total	34.84	Sqm	950	33098

19	11.46.20	Providing and fixing Ceramic glazed wall tiles 300x450 mm or more (having thickness 6 to 7 mm) of 1st quality conforming to IS: 15622 of approved make in all Colours & shades. except burgundy, bottle green, black laid on 12mm thick bed of Cement Mortar 1:3 (1 Cement: 3 sand) prepad same day when mortar is still green jointed with											
		Male ward Wall Tiles				1	6.6	1.35	8.91				
						1	3.5	1.35	4.725				
									Total	13.635	Sqm	776	10581

11.48	Providing and laying Ceramic glazed floor tiles 300x300 mm or more (having thickness 6 to 7mm) of 1st quality conforming to IS 15622 of approved make in any colours and shade laid on 20 mm thick Cement Mortar 1:4 (1 Cement: 4 sand) including pointing the joints with white cement and matching pigment etc. complete												
		main building				1	2	6.8	13.60				
		pantetid Word				3	1.3	1.3	5.07				
									Total	18.67	Sqm	670	12509

17.1	Providing and fixing water closet squatting pan (Indian type WC pan with 100 mm sand cast iron P or S trap, 1 PVC P or S trap, 10 litre low level white PVC flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required											
						2			5	Each	2995	3060

18.29	Providing and fixing brass bib cock of approved quality										
								10		306	

19.9.2	Constructing brick masonry manhole in cement mortar 1:4 (1 cement: 4 sand) R.C.C. top slab with Cement Concrete 1:2:4 mix (1 cement: 2 sand: 4 graded stone aggregate 20 mm nominal size), foundation concrete 1:2:4 mix (1 cement: 2 sand: 4 graded stone aggregate 20mm nominal size) inside plastering 12mm thick with cement mortar 1:3 (1 cement: 3 sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement: 2 sand: 4 graded stone aggregate 20mm nominal size) finished with a floating coat											
		Sewer bricks							2	Each	7747	15494
		With Sewer bricks conforming to IS 4885				3						

Item	MEASUREMENT							
	No.	L	W	D/H	Qty	Unit	Rate	Amount
	4	5	6	7	8	9	10	11
18.28	3							
18.28	1				1500	10		10500
17.29								
17.29.1	4					8 Each	1379	11032
10.4	1	1.2		2.4	2.88	Sqm	3155	9086
19.5.1								
	25					25 Mtr	576	14400
	20					20 Mtr	704	14080
19.4.1								
	5					5 Mtr	477	2385
21								
	1					1 each	3761.0	3761
22								
	1					1 each	756	756
23.18.8								
	31					31.00 Mtr	221	6851

Item		MEASUREMENT								
		No.	L	W	D/H	Qty	Unit	Rate	Amount	
3		4	5	6	7	8	9	10	11	
24		20				20.00	Mtr	300	6000	
	12.32 Providing and fixing on wall face Unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i) Single socketed pipes 12.32.2 110 mm diameter (minimum wall thickness 2.2mm)									
	Rain water	5	4.2				21	Mtr.	238	4998
25	17.59 Providing and fixing unplasticised PVC moulded fittings/ accessories for unplasticised Rigid PVC soil and waste pipes conforming to IS: 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.					30.00	Each	238	7140	
	17.59.5.2 110 mm bend	1								
26	19.7 Providing and fixing square-mouth S.W. gully trap class SP1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design :19.7.1 100x100 mm size P type						1.00	Each	1764	1764
	Chamber	1								
27	18.50.1 Providing and fixing brass bib cock of approved quality :15 mm nominal bore					10.00	Each	304	3040	
		10								
28	18.51.1 Providing and fixing brass stop cock of approved quality :15 mm nominal bore					10.00	Each	234	2340	
		10								
29	17.78 Providing and fixing C.P. brass grating of approved quality and make conforming to IS:specification. 17.78.1 100mm dia.						8.00	Each	74	592
	For toilet & Washbasin	8								
30	9.169 Providing and fixing factory made single extruded WPC(Wood Poly mer Composite) solid door/window/ceosetory windows and other frames/chowkhat comprising of virgin polymer of K value 58-60 (Suspension Grade). calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and									
	Single rebate (100 mm X50 mm)					5.2	10	R/M	720.00	7488
	Door Fram	2								

Item		MEASUREMENT							Rate	Amount	
		No.	L	W	D/H	Qty	Unit				
3		4	5	6	7	8	9	10	11		
31	9.18	9.18 Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part 1) decorative type. core of block board construction with frame of 1st class hard wood and wellmatched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters of such as duro board. century or equivalent make. 9.18.2 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.									
		1	1.2		2.1	3					
						3	Sqm	2370.0	5972		
32	9.21	9.21 Extra for providing lipping with 2nd class teak wood battens 25 mm minimum depth on all edges of flush door shutters (over all area of door shutter to be measured).									
		2	1.2		2.1	5					
						5	Sqm	401.0	2021		
33	9.192	9.192 Providing and Fixing factory made 100% solid wood plastic composite (WPC) door frames made from wood plastic composite (Single Extruded process) material with density 0.28 kg/cum and manufactured by an ISO: 9001-2000 certified company. Water absorption no more than 0.01% cum 9.192.3 WPC door frame single or double rebate (125 mm X 65 mm)									
		1	5.1			5	Mtr	980.0	4998		
34	9.2	9.191 Providing and Fixing factory made laminated 100% solid PVC flush door shutter (28mm thickness) made from rigid PVC foam sheet (Single Extruded) with density 600 kg/cum and laminated on oth sides by laminated sheet/PVC foil lamination at the manufacturing process itself. 9.191.1 9.191.2 23 mm thick pre laminated solid PVC flush door shutter									
		1	0.9		2.1	2	Sqm	3229.0	6103		
37	9.69	9.69 Providing and fixing ISI marked stainless steel handles with necessary screws etc. complete :9.69.1 125 mm									
		12				12	Each	54.0	648		
42	9.94	9.94 Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI. IS : 3564. embossed on the body. door weight upto 35 kg and door width upto 700 mm) with necessary accessories and screws etc. complete.									
		2				2	Each	780	1560		

MEASUREMENT

Item	No.	L	W	D/H	Qty	Unit	Rate	Amount
3								
9.110 Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete : 9.110.1 300x10mm	2				2	Each	123	246
9.113 Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete: 9.113.1 125mm	2				2	Each	75	150
9.84 Providing and fixing bright finished brass 100 mm mortice latch each 820.00 and lock ISI marked with six levers and a pair of anodised (anodic coating not less than grade AC 10 as per IS : 1868) aluminium lever handles with necessary screws etc. complete (Best make of approved quality).	2				2	Each	820	1640
21.5 Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315. having brand logo embossed on the body 1 plate with double spring mechanism and door weight upto 125 kg., for doors. including cost of cutting floors • embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge: 21.5.1 With stainless steel cover plate - minimum 1.25 mm each thickness	1				1	Each	2072	2072
Grand Total								443241
Add 12% GST								53189
Net Amount								496430

Sub-Engineer Health Services
Ashoknarar

Assistant Engineer
Health Services Gwalior

Executive Engineer
Health Services Gwalior